NE 195th Street Ballinger Creek Culvert Replacement

Bid Number: ####

Date: December 2019

60% DESIGN

(206) 801-2700


17500 Midvale Avenue North

Shoreline, WA 98133

DORIS MCCONNELL, DEPUTY MAYOR SUSAN CHANG KEITH MCGLASHAN CHRIS ROBERTS KEITH SCULLY BETSY ROBERTSON

DIRECTOR OF PUBLIC WORKS RANDY WITT, PE

PROJECT MANAGER



LOCATION MAP NOT TO SCALE

THIS PROJECT IS PART OF A PHASED ELEMENT OF THE CITY OF SHORELINE 25TH AVENUE NE BALLINGER CREEK FLOOD REDUCTION PROJECT.



VICINTY MAP

36

S14

SHEET INDEX									
SHEET DWG TITLE									
1	1 G1 COVER								
2	G2	LEGEND AND ABBREVIATIONS							
3	G3	GENERAL NOTES, SITE NOTES, AND TRAFFIC CONTROL NOTES							
4	G4	GENERAL ARRANGEMENT PLAN AND SURVEY NOTES							
5	C1	STREAM AND CULVERT PLAN AND PROFILE - SHEET 1 OF 2							
6	C2	STREAM AND CULVERT PLAN AND PROFILE - SHEET 2 OF 3							
7	C3	195TH ST CULVERT PLAN, SECTION, AND PROFILE							
8	C4	STREAM AND CULVERT CROSS SECTIONS							
9	C5	SEWER MAIN PROFILE							
10	C6	STREAM HABITAT DETAILS							
11	C7	POTHOLE DATA TABLE							
12	RR1	NE 195TH ST ROADWAY RESTORATION PLAN							
13	EC1	TEMPORARY EROSION AND SEDIMENT CONTROL NOTES							
14	EC2	TEMPORARY EROSION AND SEDIMENT CONTROL PLAN							
15	TC1	TEMPORARY TRAFFIC CONTROL PLAN - SHEET 1 OF 2							
16	TC2	TEMPORARY TRAFFIC CONTROL PLAN - SHEET 2 OF 2							
17	L1	PLANTING PLAN							
18	L2	PLANTING DETAILS							
19	L3	PLANT SCHEDULE							
20	L4	NOT USED AT THIS TIME							
21	L5	NOT USED AT THIS TIME							
22	L6	NOT USED AT THIS TIME							
23	S1	STRUCTURE SHEET LAYOUT AND GENERAL NOTES							
24	S2	STRUCTURAL LAYOUT - SHEET 1 OF 2							
25	S3	STRUCTURAL LAYOUT - SHEET 2 OF 2							
26	S4	WALL ELEVATIONS — SHEET 1 OF 4							
27	S5	WALL ELEVATIONS — SHEET 2 OF 4							
28	S6	WALL ELEVATIONS — SHEET 3 OF 4							
29	S7	WALL ELEVATIONS — SHEET 4 OF 4							
30	S8	CULVERT C1 PLAN AND ELEVATION							
31	S9	CULVERT C1 TYPICAL ELEVATION							
32	S10	MISCELLANEOUS DETAILS							
33	S11	SOLDIER PILE DETAILS — SHEET 1 OF 4							
34	S12	SOLDIER PILE DETAILS — SHEET 2 OF 4							
35	S13	SOLDIER PILE DETAILS - SHEET 3 OF 4							

FUNDED IN PART BY A FLOOD REDUCTION GRANT FROM THE KING COUNTY FLOOD CONTROL DISTRICT

SOLDIER PILE DETAILS - SHEET 4 OF 4

ELECTRICAL:	SEATTLE CITY LIGHT
ELECTRICAL:	(206) 684-3000
NATURAL GAS:	PUGET SOUND ENERGY
NATURAL GAS:	(888) 225-5773
	CENTURY LINK
	(800) 244-1111
TELEPHONE:	or
	FRONTIER
	(877) 462-8188
	COMCAST
	(877) 824-2288
CABLE:	or
	FRONTIER
	(877) 462-8188
WASTEWATER (SEWER):	LAKE FOREST PARK
WASTEWATER (SEWER).	(206) 368-5440
	NORTH CITY WATER DISTRICT
	(206) 362-8100
	and
WATER (SEE VICINITY MAP	
FOR SERVICE AREAS):	(206) 365-3211
	and
	SEATTLE PUBLIC UTILITIES
	(206) 684-3000
STATION MASTER/	17233 15th Ave NE
POST OFFICE:	(800) 275-8777
CALL REFORE VOLUDIO	044
CALL BEFORE YOU DIG	811

60% REVIEW SUBMITTAL NOT FOR CONSTRUCTION

APPROVED FOR CONSTRUCTION

		A S	Ž.		
	Drawn	Designed	Checked	Revisions	Revisions
Initials	JTE	JTE	MSG		
Date	12/31/19	12/31/19	12/31/19		
Description					






Shoreline, WA 98133 (206) 801-2700

NE 195TH STREET BALLINGER CREEK CULVERT REPLACEMENT
60% REVIEW SUBMITTAL

Project No. G1

Of



12/31/2019 11:42 AM - PLOT DATE

- 2. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE PROJECT PLANS AND SPECIFICATIONS. ALL WORK SHALL COMPLY WITH, IN ORDER OF PRECEDENCE:
 - * THE CITY OF LAKE FOREST PARK "ENGINEERING AND CONSTRUCTION STANDARDS", 2011.
 - * KING COUNTY "KING COUNTY ROAD STANDARDS", 2016.
 - * KING COUNTY "KING COUNTY SURFACE WATER DESIGN MANUAL", 2016.
 - * WSDOT/APWA "2020 STANDARD SPECIFICATIONS FOR ROAD, BRIDGE, AND MUNICIPAL CONSTRUCTION" (WSDOT/APWA).
- 3. THE CONTRACTOR SHALL VERIFY ALL EXISTING DATA SHOWN IN THESE DOCUMENTS AND NOTIFY ENGINEER IMMEDIATELY OF ANY CONFLICTS WITH PROPOSED FEATURES PRIOR TO CONSTRUCTION.
- 4. ALL COMPACTION METHODS, MATERIALS AND PERFORMANCE CRITERIA SHALL BE IN ACCORDANCE WITH THE PROJECT PLANS AND SPECIFICATIONS
- 5. ALL EXISTING AND PROPOSED CATCH BASINS DOWNSTREAM OF DISTURBED AREAS SHALL BE PROTECTED DURING CONSTRUCTION PER THE WSDOT STD PLAN I-7.
- 6. ALL PIPE LENGTHS, INVERT ELEVATIONS AND DRAINAGE STRUCTURE LOCATIONS ARE MEASURED AT THE CENTER OF THE DRAINAGE STRUCTURE UNLESS NOTED OTHERWISE.
- 7. ALL LOCATIONS OF EXISTING UTILITIES SHOWN HAVE BEEN ESTABLISHED BY FIELD SURVEY OR OBTAINED FROM AVAILABLE RECORDS AND SHOULD THEREFORE BE CONSIDERED APPROXIMATE ONLY AND NOT NECESSARILY COMPLETE. IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE ACCURACY OF ALL UTILITY LOCATIONS SHOWN AND AVOID EXISTING UTILITIES, INCLUDING OTHER UTILITIES NOT SHOWN ON THE PLANS. EXISTING UTILITIES SHALL BE PROTECTED, SUPPORTED, OR MAINTAINED DURING CONSTRUCTION.
- 8. CONTACT THE UNDERGROUND UTILITIES LOCATION SERVICE (811 / WWW.CALL811.COM) AT LEAST 48 HOURS PRIOR TO CONSTRUCTION.
- 9. ALL WORK SHALL CONFORM TO THESE APPROVED PLANS AND SPECIFICATIONS, THE LAKE FOREST PARK MUNICIPAL CODE, THE ENGINEERING DEVELOPMENT MANUAL, AND FEDERAL AND STATE REQUIREMENTS.

GENERAL NOTES

- 1. THE CITY OF SHORELINE IS THE PROJECT PROPONENT. AS A PROJECT PROPONENT THE CITY OF SHORELINE WILL BE A JOINT REVIEWER OF MOST CONSTRUCTION ACTIVITIES AND SUBMITTALS. REFERENCES TO ENGINEER INCLUDE BOTH THE CITY OF LAKE FOREST PARK AND CITY OF SHORELINE.
- 2. MAINTAIN CONVEYANCE OF STORM DRAINAGE AND STREAM FLOWS DURING CONSTRUCTION AND DURING THE REPLACEMENT, MODIFICATION OR RESTORATION OF EXISTING FACILITIES IN ACCORDANCE WITH CONTRACTOR'S APPROVED BYPASS PLAN. SEE SPECIAL PROVISIONS.
- 3. OVERHEAD ELECTRICAL POWER, TELEPHONE, CABLE TV, AND OTHER OVERHEAD LINES ARE APPROXIMATELY SHOWN. DETERMINE THE EXTENT OF HAZARDS OR IMPACTS ON CONSTRUCTION ACTIVITIES CREATED BY OVERHEAD OR UNDERGROUND ELECTRICAL POWER, TELEPHONE, CABLE TV, AND OTHER LINES IN ALL AREAS, AND FOLLOW PROCEDURES DURING CONSTRUCTION AS REQUIRED BY LAW AND REGULATIONS. TAKE PRECAUTIONS AND REMEDIAL MEASURES THAT MAY BE REQUIRED TO PROTECT PERSONS AND PROPERTY AND TO AVOID DISRUPTION OF SERVICE.
- 4. NO WORK SHALL COMMENCE PRIOR TO A PRE-CONSTRUCTION CONFERENCE.
- 5. CONTRACTOR TO PROVIDE CONTINUOUS ACCESS FOR EMERGENCY VEHICLES AND HOMEOWNERS DURING
- 6. DISPOSAL OF MATERIAL SHALL BE IN ACCORDANCE WITH LOCAL, STATE, AND FEDERAL REQUIREMENTS.
- 7. WORK IN BALLINGER CREEK SHALL BE PERFORMED ACCORDING TO THE REQUIREMENTS OF THE HYDRAULIC PROJECT APPROVAL (HPA) PERMIT OBTAINED BY THE CITY OF SHORELINE/ LAKE FOREST PARK. WORK SHALL BE LIMITED TO THE DESIGNATED TIME FRAME AS STATED IN THE APPROVED HPA. A COPY OF WHICH IS INCLUDED IN THE SPECIAL PROVISIONS, APPENDIX A.

SITE NOTES (SN)

- SN.1. THE CONTRACTOR SHALL HAVE ANY REQUIRED PERMIT(S) AND CONDITIONS AND THE APPROVED PLANS AVAILABLE AT THE JOB SITE.
- SN.2. ALL INSTALLATION METHODS AND MATERIALS SHALL MEET THE WSDOT/APWA STANDARD SPECIFICATIONS UNLESS SUPERCEDED BY THESE PLANS AND SPECIFICATIONS.
- SN.3. ANY CHANGES FROM THE APPROVED PLANS REQUIRE PRE-APPROVAL FROM THE ENGINEER.
- SN.4. THE CONTRACTOR ASSUMES SOLE RESPONSIBILITY FOR WORKER SAFETY AND DAMAGE FROM CONSTRUCTION OPERATIONS TO STRUCTURES AND OTHER IMPROVEMENTS.
- SN.5. SURVEYING FOR PUBLIC FACILITIES SHALL BE PERFORMED UNDER THE DIRECTION OF A WASHINGTON LICENSED LAND SURVEYOR. VERTICAL DATUM SHALL BE NAVD 1988. HORIZONTAL DATUM SHALL BE WASHINGTON STATE (GRID) COORDINATES, NORTH ZONE, USING NAD 83/91 SURVEY CONTROL AND TO ANY TWO CITY OF SHORELINE HORIZONTAL CONTROL MONUMENTS. FOR PROJECTS WITHIN A FLOOD CONTROL ZONE, THE SURVEYOR SHALL PROVIDE CONVERSION CALCULATIONS TO NGVD 1929.
- SN.6. REPLACE OR RELOCATE ALL SIGNS, STRIPING, POLES AND OTHER ITEMS IN THE RIGHT-OF-WAY THAT
- SN.7. RETAIN, REPLACE OR RESTORE ALL VEGETATION IN RIGHTS-OF-WAY, EASEMENTS, AND ACCESS TRACTS
- SN.8. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ADEQUATE SAFEGUARDS, SAFETY DEVICES, PROTECTIVE EQUIPMENT, FLAGGERS, AND ANY OTHER NEEDED ACTIONS TO PROTECT THE LIFE, HEALTH, AND SAFETY OF THE PUBLIC, AND TO PROTECT PROPERTY IN CONNECTION WITH THE PERFORMANCE OF WORK COVERED BY THE CONTRACTOR. ANY WORK WITHIN THE TRAVELED RIGHT-OF-WAY REQUIRES A RIGHT-OF-WAY USE PERMIT, TO BE REVIEWED PRIOR TO CONSTRUCTION AND INSPECTED DURING
- SN.9. THE CONTRACTOR SHALL RESTORE CRITICAL AREAS AND PUBLIC AND PRIVATE PROPERTY DAMAGED BY CONTRACTOR'S OPERATIONS TO CURRENT STANDARDS.
- SN.10. AT ALL TIMES MAINTAIN ACCESS TO BUILDINGS FOR FIRE, PEDESTRIAN AND VEHICULAR ACCESS.
- SN.11. ALL UTILITY TRENCHES AND ROADWAY SUBGRADES WITHIN CITY RIGHT-OF-WAY SHALL BE BACKFILLED AND COMPACTED IN ACCORDANCE WITH KING COUNTY ROAD STANDARDS WITH 100% CRUSHED SURFACING COURSE OR CONTROLLED DENSITY FILL (CDF).
- SN.12. WHERE TREES ARE SHOWN TO BE PROTECTED, CONTRACTOR TO SET FLAGGING AROUND TREE AT DROP LINE UNLESS OTHERWISE DIRECTED BY ENGINEER.

TRAFFIC CONTROL NOTES (TC)

- TC.1. MAINTENANCE OF TRAFFIC: A PRELIMINARY TRAFFIC CONTROL PLAN HAS BEEN PREPARED TO SECURE PROJECT PERMITS AND IS INCLUDED AS PART OF THE PLANS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR TEMPOARARY TRAFFIC CONTROL DURING CONSTRUCTION ON OR ALONG TRAVELED
- TC.2. ANY CHANGE TO THE TRAFFIC CONTROL PLAN SHALL BE SUBMITTED BY THE CONTRACTOR FOR APPROVAL BY WSDOT AND LAKE FOREST PARK 10 DAYS PRIOR TO BEGINNING THE WORK. TRAFFIC CONTROL SHALL FOLLOW THE GUIDELINES OF SECTION 1-07.23 OF THE WSDOT/APWA STANDARD SPECIFICATIONS AS AMENDED BY THESE PLANS AND SPECIFICATIONS
- TC.3. ALL BARRICADES, SIGNS AND FLAGGING SHALL CONFORM TO THE REQUIREMENTS OF THE MUTCD, FOR MORE SPECIFIC REQUIREMENTS FOR BARRICADES, SEE SECTION 5.7 AND DRAWING NO. 5-003 OF KING COUNTY ROAD STANDARDS. SIGNS MUST BE LEGIBLE AND VISIBLE AND SHALL BE REMOVED AT THE END OF EACH WORK DAY IF NOT APPLICABLE AFTER CONSTRUCTION HOURS.
- TC.4. TEMPORARY ROAD CLOSURES AND DETOURS: WHEN TEMPORARY ROAD CLOSURES CANNOT BE AVOIDED THE CONTRACTOR SHALL POST "TO BE CLOSED" SIGNS A MINIMUM OF FIVE DAYS PRIOR TO THE CLOSING. THE TYPES AND LOCATIONS OF THE SIGNS SHALL BE SHOWN ON A DETOUR PLAN.
- TC.5. A DETOUR PLAN MUST BE PREPARED AND SUBMITTED TO THE CITY OF LAKE FOREST PARK AND WSDOT AT LEAST 10 WORKING DAYS IN ADVANCE, AND APPROVED PRIOR TO CLOSING ANY CITY ROAD. IN ADDITION, THE CONTRACTOR MUST NOTIFY, IN WRITING, LOCAL FIRE, SCHOOL, LAW ENFORCEMENT AUTHORITIES, METRO TRANSIT, AND ANY OTHER AFFECTED PERSONS AS DIRECTED BY THE ENGINEER AT LEAST FIVE DAYS PRIOR TO CLOSING.
- TC.6. A HAUL ROUTE PLAN MUST BE SUBMITTED TO THE CITY OF LAKE FOREST PARK AND WSDOT FOR APPROVAL PRIOR TO BEGINNING CONSTRUCTION. THE HAUL ROUTE PLAN SHALL ADDRESS ROUTING, HOURS OF OPERATION, SIGNAGE AND FLAGGING, AND DAILY MAINTENANCE.
- TC.7. IF THE CONTRACTOR'S TRAFFIC FAILS TO USE THE DESIGNATED HAUL ROUTE, THE ENGINEER MAY PROHIBIT OR LIMIT FURTHER WORK ON THE DEVELOPMENT UNTIL SUCH TIME AS THE REQUIREMENTS OF THE HAUL ROUTE ARE COMPLIED WITH.
- TC.8. FLAGGING SHALL BE MAINTAINED BY THE CONTRACTOR FOR THE DURATION OF CONSTRUCTION. INTERRUPTION OF NORMAL TRAFFIC FLOW SHALL REQUIRE TRAFFIC CONTROL
- TC.9. CONTRACTOR SHALL PROTECT EXISTING TRAFFIC CONTROL SIGNS WITHIN THE LIMITS OF WORK.

W 1/2 SW 1/4 SEC 08, T26N, R1E, WM

Description									
Date	12/31/19	12/31/19	12/31/19						
nitials	JTE		MSG						
	Drawn	Designed JTE	Checked	Revisions	Revisions				





7500 Midvale Ave. N Shoreline, WA 98133 (206) 801-2700

> \triangleleft AL

195TH STREET BALLINGER CREEK CULVERT REPLACEMENT


10% REVIEW SUBMITTA CE NOT 60% REVIEW SUF ENERAL NOTES, SITE TRAFFIC CONTROL

Call before you dig

Project No. ____

G3

12/31/2019 11:42 AM - PLOT DATE



DATUM / PROJECT CONTROL

LEGAL DESCRIPTION:

PORTION OF THE W. $\frac{1}{2}$ OF THE SW. $\frac{1}{4}$ OF SECTION 8, TOWNSHIP 26 NORTH, RANGE 1 EAST, WILLAMETTE MERIDIAN, CITY OF LAKE FOREST PARK, KING COUNTY, STATE OF WASHINGTON.

HORIZONTAL DATUM / BASIS OF BEARINGS:

NORTH AMERICAN DATUM OF 1983 (ADJUSTED 1991) -NAD83(91). WASHINGTON STATE PLANE COORDINATE SYSTEM - NORTH ZONE.

NORTH 04°21'48" EAST ALONG THE WEST LINE OF THE SW. 14 OF SECTION 8 (CENTERLINE OF MERIDIAN AVENUE NORTH).

VERTICAL DATUM / BASIS OF ELEVATIONS:

NORTH AMERICAN VERTICAL DATUM OF 1988 - NAVD88.

DATES OF FIELD SURVEYS: 07/25/2018, 08/06/2018 BY 1ALLIANCE GEOMATICS.

BUILDING OUTLINES HAVE BEEN DIGITIZED FROM GIS AERIAL 2019 AND ARE APPROXIMATE ONLY.

now what's below. Call before you dig

빌빌






17500 Midvale Ave. N Shoreline, WA 98133 (206) 801-2700

NE 195TH STREET BALLINGER CREEK CULVERT REPLACEMENT 60% REVIEW SUBMITTAL GENERAL ARRANGEMENT AND SURVEY NOTES

Project No.

G4

4 Of 12/31/2019 11:42 AM - PLOT DATE



GENERAL NOTES

- 1. ALL WORK THIS SHEET IS WITHIN CITY OF LAKE
- 2. LIMIT DISTURBANCE TO ONLY THOSE AREAS NECESSARY FOR CONSTRUCTING THE PROPOSED IMPROVEMENTS.
- 3. SEE CHANNEL SECTIONS ON DWG C4.
- 4. PROTECT EXISTING LANDSCAPING AND VEGETATION. WHERE DISTURBED OR REMOVED DURING CONSTRUCTION, RESTORE SURFACE FEATURES IN KIND.
- 5. EXISTING 30" DIA CMP CULVERT IS LISTED ON WSDOT FISH PASSAGE REPLACEMENT PROGRAM AND WILL LIKELY BE REPLACED PRIOR TO 2030. IT IS ANTICIPATED THAT REPLACEMENT CULVERT WILL NEED TO BE DEEPER AT ITS INLET TO MEET FISH PASSAGE REQUIREMENTS. THE PROFILE FOR BALLINGER CREEK COULD BE LOWERED AT THAT TIME AND A POSSIBLE FUTURE STREAM PROFILE IS SHOWN.

5 **O**f 36 12/31/2019 1:27 PM - PLOT DATE

C1

Project No.

빌

Louis Berger 1301 Fifth Ave, Ste 1200

SHORELINE

 A_{Z}

REVIEW A AND CUL

60% R REAM

OF

SHEET

PROFILE

17500 Midvale Ave. N

Shoreline, WA 98133 (206) 801-2700

NE 195TH STREET BALLINGER CREEK CULVERT REPLACEMENT

Seattle, WA 98101

KEYED NOTES

1 NEW SOLIDER PILE WALL (TO REPLACE GABION WALL) SEE DWGS S1 THROUGH S14.

 $\langle 2 \rangle$ HABITAT LOG, TYP. SEE DETAIL 1 ON DWG C6. QTY=1.

3 HABITAT LOG STRUCTURE TYPE 1, TYP. SEE DETAIL 2 ON DWG C6. QTY=2.


4 HABITAT LOG STRUCTURE TYPE 2, TYP. SEE DETAIL 3 ON DWG C6. QTY=4.

(5) REMOVE EXISTING GABION WALL FROM APPROX STA 12+70 TO 15+70. SEE SPECIFICATIONS FOR ORIGINAL 1980 GABION WALL DESIGN INFORMATION.

6 PROTECT EXISTING TREES.

7 INSTALL TYPE 3 PEDESTRIAN FENCE PER WSDOT STANDARD DETAIL L-20.10-03.

Scale



(13)

REMOVE EXISTING CHAIN LINK FENCE TO PROVIDE ACCESS FOR NEW WALL. REPLACE WITH TYPE 3 PEDESTRIAN FENCE

PER WSDOT STANDARD DETAIL L-20.10-03.

EDGE OF NEW CULVERT, NOT CENTERLINE OF STREAM

 $\langle 6
angle$ remove and dispose of existing culvert.

Know what's below. Call before you dig. Sheet

IMPROVEMENTS WILL BE IN PLACE DEPENDS ON PROJECT PHASING. IF THIS PROJECT PRECEDES THE

SHORELINE PROJECT THERE WILL NEED TO BE A ROUGHENED/ROCK LINED CHANNEL TRANSITION.

7. SEE GENERAL NOTE 5 ON DWG C1.

12/31/2019 1:40 PM - PLOT DATE


36


6 **O**f

OF


 \sim

SHEET





- CONSTRUCT 4.0' TALL PEDESTRIAN RAIL PER WSDOT STD PLAN L-20.10-03.
- REMOVE EXISTING GABION WALL.
- SEE SHEETS L1 THROUGH L3 FOR PLANTING AND SOIL AMENDMENT.









17500 Midvale Ave. N Shoreline, WA 98133 (206) 801-2700


NE 195TH STREET BALLINGER CREEK CULVERT REPLACEMENT 60% REVIEW SUBMITTAL STREAM AND CULVERT CROSS SECTIONS


Project No.


36 8 **O**f

















17500 Midvale Ave. N Shoreline, WA 98133 (206) 801-2700

S

NE 195TH STREET BALLINGER CREEK CULVERT REPLACEMENT 60% REVIEW SUBMITTAL STREAM HABITAT DETAIL


GENERAL NOTES

HABITAT LOGS SHALL BE 2/3 EMBEDDED (BY LENGTH) IN STREAM BANK.

Call before you dig. Sheet

Project No. C6

> 10 Of 36 12/31/2019 11:47 AM - PLOT DATE



STEEL CASING NOTES:

- 1. CASING SPACERS SHALL BE "CENTER POSITIONING TYPE". MINIMUM RUNNER WIDTH SHALL BE 2".
- 2. RUNNER HEIGHT SHALL BE SIZED TO PROVIDE: A. MIN 4" CLEARANCE BETWEEN CARRIER PIPE AND CASING PIPE. B. MIN 1" CLEARANCE BETWEEN RUNNERS AND TOP OF CASING WALL TO PREVENT JAMMING DURING INSTALLATION.
- 3. STEEL CASING DIAMETER IS OUTSIDE DIAMETER.
- ANTICORROSIVE COATING THICKNESS CASING 3 MILLS. HOT DIP GALVANIZED IN ACCORDANCE WITH

DETAIL (5) (C5) STEEL SEWER CASING

EXISTING UTILITY DATA	1								
POTHOLE # (1)	TYPE OF UTILITY	MATERIAL	SIZE OF UTILITY	GROUND EL	MEASUREMENT TO TOP OF UTILITY	MEASUREMENT TO BOTTOM OF UTILITY	APPROX. EL OF BOTTOM OF UTILITY	DISTANCE FROM FOG LINE/CENTER LINE/CURB	NOTES
1	WATER	STEEL	8"	213.23'	37.5"	45.5"	209.44'	2'2" / 13'5" / N/A	PIPE RUSTY
2	WATER	STEEL	66"	213.14'	38.0"	104.0"	204.47'	1'3" / 13'8" / 4'3"	
10	СОМ	PVC	(2) 4"	213.82'	30.0"	37.0"	210.74	1'3" / 18'11" / 7'2"	
12	WATER	STEEL	66"	215.21'	46.0"	112.0"	205.88'	8'9" / 13'4" / 9'9"	
13	WATER	STEEL	66"	212.92'	37.0"	103.0"	204.34'	2'6" / 14'3" / 2'10"	

NOTES:
1. SEE DWG C5 FOR POTHOLE LOCATIONS.

Initials
JTE 12
JTE 12
MSG 12






17500 Midvale Ave. N Shoreline, WA 98133 (206) 801-2700

NE 195TH STREET BALLINGER CREEK CULVERT REPLACEMENT 60% REVIEW SUBMITTAL


Project No. C7

11 Of 36



KEYED NOTES

- INSTALL 30 LF CURB AND GUTTER PER LFP STD DTL 2.06.
- INSTALL 18 SY 6' WIDE CEMENT CONCRETE SIDEWALK PER LFP STD DTL 2.12.
- RESTORE UTILITY TRENCH PER LFP STD DTL 2.14 (TYP).
- RESTORE DOUBLE CENTERLINE PER WSDOT STD PLAN M-20.10-02.
- RESTORE SOLID EDGE LINE PER WSDOT STD PLAN M-20.10-02.
- RESTORE TRAFFIC LOOP IN KIND.
- RESTORE AREA BETWEEN EDGE OF PAVEMENT AND NEW CULVERT HEADWALL WITH GRAVEL SHOULDER.
- INSTALL 4.0' HIGH PEDESTRIAN FENCE PER WSDOT STANDARD PLAN L-20.10-03.
- INSTALL GRASSCRETE OR EQUIVALENT PRODUCT FOR VEHICLE ACCESS.



- NOTES:

 1. SUBGRADE SHALL BE COMPACTED TO 95% UNDER ROAD, CURB, GUTTER, AND SIDEWALK.
- 2. COMPACTION TEST MAY BE REQUIRED.

Project No.

Initials JTE JTE

Louis Berger
1301 Fifth Ave, Ste 1200

SHORELINE

17500 Midvale Ave. N Shoreline, WA 98133 (206) 801-2700

NE 195TH STREET BALLINGER CREEK
CULVERT REPLACEMENT
60% REVIEW SUBMITTAL
NE 195TH ST ROADWAY
RESTORATION PLAN

RR1 12 Of 36

12/31/2019 11:49 AM - PLOT DATE

EROSION AND SEDIMENTATION CONTROL REQUIREMENTS (TESC)

- TESC.1. THE IMPLEMENTATION AND MAINTENANCE OF EROSION CONTROL FACILITIES IS THE RESPONSIBILITY OF THE CONTRACTOR ON A DAILY BASIS AND UNTIL ALL CONSTRUCTION IS APPROVED.
- TESC.2. AT ALL TIMES PROTECT CRITICAL AREAS AND THEIR BUFFERS, ADJACENT PRIVATE PROPERTIES AND PUBLIC PROPERTY AND SURVEY MONUMENTS.
- TESC.3. EROSION SEDIMENTATION CONTROL (ESC) FACILITIES MUST BE CONSTRUCTED PRIOR TO AND IN CONJUNCTION WITH ALL CLEARING AND GRADING ACTIVITIES, AND IN SUCH A MANNER AS TO ENSURE THAT SEDIMENT-LADEN WATER OR AIRBORNE SEDIMENT DOES NOT ENTER DRAINAGE OR STREAM FLOW CONVEYANCE SYSTEM OR VIOLATE APPLICABLE WATER OR AIR QUALITY STANDARDS DURING THE CONSTRUCTION PERIOD. THESE ESC FACILITIES SHALL BE UPGRADED TO INCLUDE ADDITIONAL SUMPS, DITCHES, FENCES, ETC. AS NEEDED FOR UNEXPECTED STORM EVENTS.
- TESC.4 STABILIZED CONSTRUCTION ENTRANCES AND WASH PADS SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT. ADDITIONAL MEASURES MAY BE REQUIRED BY THE CITY OF LAKE FOREST TO ENSURE THAT PAVED AREAS ARE KEPT CLEAN FOR THE
- TESC.5. ANY AREA STRIPPED OF VEGETATION (INCLUDING ROADWAY EMBANKMENTS), WHERE NO FURTHER WORK IS ANTICIPATED FOR A PERIOD OF 2 DAYS, SHALL BE IMMEDIATELY STABILIZED WITH APPROVED ESC METHODS AS FOLLOWS.
 - FROM MAY 1 THROUGH SEPTEMBER 30. INSTALL TESC COVER MEASURES TO PROTECT DISTURBED AREAS THAT WILL REMAIN UNWORKED FOR SEVEN DAYS OR MORE.
 - FROM OCTOBER 1 THROUGH APRIL 30:
 - A) INSTALL TESC COVER MEASURES TO PROTECT DISTURBED AREAS THAT WILL REMAIN UNWORKED
 - B) PROTECT STOCKPILES AND STEEP CUT/FILL SLOPES IF UNWORKED FOR MORE THAN 12 HOURS C) STOCKPILE ON SITE ENOUGH COVER MATERIALS TO COVER ALL DISTURBED AREAS. ANÝ AREA NEEDING ESC MEASURES, NOT REQUIRING IMMEDIATE ATTENTION, SHALL BE ADDRESSED
- TESC.6. ESC FACILITIES ON INACTIVE SITES SHALL BE INSPECTED AND MAINTAINED A MINIMUM OF ONCE A MONTH OR WITHIN 48 HOURS FOLLOWING A STORM EVENT.
- TESC.7. BY OCTOBER 8, SEED ALL AREAS THAT WILL REMAIN UNWORKED FROM OCTOBER 1 THROUGH APRIL 30.
- TESC.8. AT NO TIME SHALL MORE THEN ONE (1) FOOT OF SEDIMENT BE ALLOWED TO ACCUMULATE WITHIN A CATCH BASIN. ALL CATCH BASINS & CONVEYANCE LINES SHALL BE CLEANED PRIOR TO PAVING. THE CLEANING OPERATION SHALL NOT FLUSH SEDIMENT-LADEN WATER INTO A DOWNSTREAM SYSTEM.
- TESC.9. WHERE SEEDING FOR TEMPORARY EROSION CONTROL IS REQUIRED. FAST-GERMINATING GRASSES SHALL BE APPLIED AT AN APPROPRIATE RATE (E.G. ANNUAL OR PERENNIAL RYE APPLIED AT APPROXIMATELY 80 POUNDS PER ACRE). WHERE STRAW MULCH FOR TEMPORARY EROSION CONTROL IS REQUIRED, IT SHALL BE APPLIED AT A MINIMUM THICKNESS OF TWO INCHES.
- TESC.10. THE EROSION PREVENTION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICES SHOWN ON THE TESC ARE MINIMUM REQUIREMENTS. FIELD ADJUSTMENTS SHALL BE MADE TO ENSURE THE TESC PERFORMS IN ACCORDANCE WITH THE 2019 DEPARTMENT OF ECOLOGY STORMWATER MANAGEMENT MANUAL FOR WESTERN WASHINGTON, VOLUME II.
- TESC.11. BEFORE ANY GROUND DISTURBANCE OCCURS ALL DOWNSTREAM BEST MANAGEMENT PRACTICES MUST BE CONSTRUCTED AND OPERATIONAL
- TESC.12. BEST MANAGEMENT PRACTICES SHALL REMAIN IN PLACE UNTIL FINAL SITE CONSTRUCTION IS COMPLETED AND PERMANENT STABILIZATIONS IS ESTABLISHED AND APPROVED BY THE CITY.
- TESC.13. INSPECT AND MAINTAIN BEST MANAGEMENT PRACTICES DAILY IN ACCORDANCE WITH THE 2019 DEPARTMENT OF ECOLOGY STORMWATER MANAGEMENT MANUAL FOR WESTERN WASHINGTON. VOLUME II.
- TESC.14. FAILURE TO MAINTAIN TESC MEASURES IN ACCORDANCE WITH ADOPTED STANDARDS MAY RESULT IN THE WORK BEING PERFORMED AT THE CITY'S DIRECTION AND THE COSTS DEDUCTED FROM MONIES
- TESC.15. DURING THE LIFE OF THE PROJECT, THE CONTRACTOR SHALL MAINTAIN IN GOOD CONDITION AND PROMPTLY REPAIR, RESTORE OR REPLACE ALL GRADE SURFACES; WALLS, DRAINS, DAMS, STRUCTURES, VEGETATION, TESC MEASURES, AND OTHER PROTECTIVE DEVICES IN ACCORDANCE WITH APPROVED
- TESC.16. THE CONTRACTOR SHALL MONITOR DOWNSTREAM DRAINAGE FEATURES, AND, WITH THE CITY'S APPROVAL, SHALL REMOVE ALL SEDIMENT DEPOSITION RESULTING FROM THE PROJECT-RELATED WORK.
- TESC.17. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH ALL FEDERAL, STATE, AND LOCAL LAWS.
- TESC.18. BEFORE REMOVING ANY TEMPORARY MEASURES, INSTALL AND ESTABLISH THE UPSTREAM PERMANENT MEASURES.
- TESC.19. ALL TESC MEASURES SHALL BE IN COMPLIANCE WITH THE NPDES PERMIT. THE CONTRACTOR SHALL TRACK THE INSPECTION RESULTS AND MAINTENANCE ACTIVITIES IN THE MONITORING LOG.
- TESC 20. THE CONTRACTOR MUST MAINTAIN A SWEEPER ON SITE DURING FLOODPLAIN STORAGE AREA EARTHWORK AND IMMEDIATELY REMOVE SOIL THAT HAS BEEN TRACKED ONTO PAVED AREAS AS A RESULT OF CONSTRUCTION. THE PAVEMENT SHALL BE CLEANED AT THE END OF EACH CONSTRUCTION DAY IF SEDIMENT IS DEPOSITED ONTO THE PAVEMENT DUE TO CONSTRUCTION ACTIVITY AND/OR VEHICLES. SWEEPER MUST BE VACUUM TYPE SWEEPER WITH DUST CONTROL. SIMPLE BROOM TYPE
- TESC.21. THE CONTRACTOR SHALL MONITOR DISCHARGE FROM THE SITE. SITE DISCHARGE SHALL MEET ALL LOCAL, CITY, STATE, AND FEDERAL REQUIREMENTS FOR WATER QUALITY INCLUDING TURBIDITY AND PH

CITY OF LAKE FOREST PARK STANDARD TESC NOTES

- ALL SEDIMENT CONTROL MEASURES TO BE ADJUSTED TO MEET FIELD CONDITIONS AT THE TIME OF CONSTRUCTION, AND BE CONSTRUCTED PRIOR TO ANY GRADING OR DISTURBANCE OF EXISTING SURFACE MATERIAL ON BALANCE OF SITE.
- 2. PERIODIC INSPECTION AND MAINTENANCE OF ALL SEDIMENT CONTROL STRUCTURES MUST BE PROVIDED TO ENSURE INTENDED PURPOSE IS ACCOMPLISHED. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL SEDIMENT LEAVING THE PROPERTY. SEDIMENT CONTROL MEASURES SHALL BE IN WORKING CONDITION AT THE END OF EACH WORKING DAY.
- 3. THE SEDIMENT CONTROL MEASURES WILL BE MAINTAINED ON A CONTINUING BASIS UNTIL THE SITE IS PERMANENTLY STABILIZED AND ALL PERMIT REQUIREMENTS ARE MET.

SITE GRADING CONDITIONS (SG)

- SG.1. ALL DISTURBED AREAS INCLUDING FACES OF CUT AND FILL SLOPES SHALL BE PREPARED AND MAINTAINED TO CONTROL EROSION. THIS CONTROL MAY CONSIST OF EFFECTIVE PLANTING. THE PROTECTION FOR THESE AREAS SHALL BE INSTALLED AND MAINTAINED AS SOON AS PRACTICAL AND PRIOR TO BOND
- SG.2. PROVISIONS SHALL BE MADE TO PREVENT ANY SURFACE WATER OR SEEPAGE FROM DAMAGING THE CUT FACE OF ANY EXCAVATION OR THE SLOPING FACE OF A FILL. CARRY ANY SURFACE WATER THAT IS OR MIGHT BE CONCENTRATED AS A RESULT OF A FILL OR EXCAVATION TO A NATURAL WATERCOURSE OR DESIGNATED RETENTION FACILITY. PREVENT ANY SEDIMENT FROM LEAVING THE SITE.
- SG.3. SIGNS OF WARNING OF HAZARDOUS CONDITIONS, IF SUCH EXIST, SHALL BE AFFIXED AT LOCATIONS AS REQUIRED BY THE ENGINEER.
- SG.4. FENCING, WHERE REQUIRED, TO PROTECT LIFE, LIMB AND PROPERTY, SHALL BE INSTALLED WITH LOCKABLE GATES WHICH MUST BE CLOSED AND LOCKED WHEN NOT WORKING THE SITE. THE FENCE MUST BE NO LESS THAN FIVE (5) FEET IN HEIGHT AND THE FENCE MATERIAL SHALL HAVE NO HORIZONTAL OPENING LARGER THAN TWO (2) INCHES.
- SG.5. THE TOPS AND THE TOES OF CUT AND FILL SLOPES SHALL BE SET BACK FROM STRUCTURES AS FAR AS IS NECESSARY FOR ADEQUACY OF FOUNDATION SUPPORT AND TO PREVENT DAMAGE AS A RESULT OF WATER RUNOFF OR EROSION OF THE SLOPES.

W 1/2 SW 1/4 SEC 08. T26N. R1E. WM

Description						
Date	12/31/19	12/31/19	12/31/19			
Initials	JTE	JTE	MSG			
	Drawn	Designed	Checked	Revisions	Revisions	
	()		





17500 Midvale Ave. N Shoreline, WA 98133 (206) 801-2700

NA P ET BALLINGER CREEK I REPLACEMENT IEW SUBMITTAL RY EROSION AND NOTE CULVERT R CULVERT R 10% REVIE TEMPORAR


60% TE


NE


Call before you dig.

Project No.

13 Of 36 12/31/2019 11:50 AM - PLOT DATE













17500 Midvale Ave. N Shoreline, WA 98133 (206) 801-2700

TC2 16 Of 36



12/30/2019 8:26 PM - PLOT DATE



MULCH TREES AND SHRUBS ABOVE THE ORDINARY HIGH WATER (OHW) LINE. MULCH USING ARBORIST WOOD CHIP MULCH (SEE SPECIFICATIONS).


2. STAKE OR MARK OHW LINE IN FIELD PRIOR TO PLANTING TO ENSURE MULCH IS PLACED CORRECTLY.

DETAIL - BAREROOT TREE OR SHRUB PLANTING

SCALE: NTS







SCALE: NTS

DETAIL - LIVE STAKE PLANTING LAYOUT, TYP.

GROUP EACH SPECIES OF WILLOW IN UNEVEN CLUSTERS (TYP.)


PLANTING LAYOUT NOTES:

- PLANT WILLOW, BLACK COTTONWOOD, AND REDOSIER DOGWOOD STAKES AS SHOWN ON PLAN. SHRUBS SHALL BE IN CLUSTERS OF UNEVEN NUMBERS (E.G. THREE, FIVE, AND SEVEN.) BLACK COTTONWOOD SHALL NOT BE PLANTED AS A CLUSTER.
- PLANTS SHALL BE SPACED 4 FEET APART, ARRANGED SO THAT AS THEY MATURE, THEY GROW IN TO MASSINGS AND FULLY COVER THE SOIL SURFACE.



DETAIL - TREE-SHRUB BARE ROOT PLANTING LAYOUT






1. SOAK BOTTOM 6" OF ALL STAKES IN WATER FOR MINIMUM OF 24 HOURS PRIOR TO PLANTING

LIVE WILLOW STAKE PLANTING DETAIL

SCALE: NTS



- PLANT GROUNDCOVERS, SHRUBS, AND TREES AS SHOWN IN DETAIL, 3 FEET O.C. GROUNDCOVERS AND SHRUBS SHALL BE IN CLUSTERS OF UNEVEN NUMBERS (E.G. THREE, FIVE, SEVEN, ETC.) IN GROUPINGS NO LARGER THAN NINE
- PLANTS SHALL BE ARRANGED SO THAT AS THEY MATURE, THEY GROW IN TO MASSINGS AND FULLY
- PLANTS ARE PLANTED CLOSELY TOGETHER TO COMPETE WITH INVASIVE PLANT SPECIES WITH MINIMUM MAINTENANCE.

12/31/19

RG 8

1301 Fifth Ave, Ste 1200 Seattle, WA 98101

SHORELINE

SUBMITTAL

60% REVIEW

PLANTING DETAILS

17500 Midvale Ave. N

Shoreline, WA 98133 (206) 801-2700

195TH STREET BALLINGER CREEK

NE

CULVERT REPLACEMENT

Call before you dig

Sheet 18 **Of** 36

SCALE: NTS

COVER THE SOIL SURFACE.

				PLANTING ZONES*						
LATIN NAME Trees	COMMON NAME	MATURE HEIGHT	STOCK TYPE	SPACING ON CENTER (FEET)	WS-3 (WETLAND SHRUB)	RB-2 (RIPARIAN BUFFER)	RB-3 (RIPARIAN BUFFER)	WS-4 (WETLAND SHRUB)	UB-2 (UPLAND BUFFER)	QUANTITY
11663	T	1	<u> </u>							
Acer grandidentatum 'Schmidt'	Rocky Mountain Glow maple	25'	1"-1.5" Cal. B&B**	10'						
Acer macrophyllum	Bigleaf maple	90'	36"+ BRS	10'			6			6
Fraxinus latifolia	Oregon ash	80'	36"+ BRS	10'		4	6			10
Populus balsamifera ssp. trichocarpa	Black cottonwood	150'	4' Live Stakes	41	11			24		35
Pseudotsuga menziesii	Douglas fir	200'	Plug-15	10'			6			6
Thuja plicata	Western redcedar	150'	Plug-15	10'		2	6			8
Tsuga heterophylla	Western hemlock	150'	Plug-15	10'		2	6			8
Shrubs										
Amelanchier alnifolia	Saskatoon serviceberry	15'	18"-36" BRS	10'		1	4			5
Cornus sericea var. stolonifera	Red-osier dogwood	12'	4' Live Stakes	4'	28			71		99
Lonicera involucrata	Twinberry honeysuckle	6'	18"-36" BRS	4'					55	55
Mahonia aquifolium	Hollyleaved barberry	12'	18"-36" BRS	6'		3	7		18	28
Mahonia nervosa	Cascade barberry	4'	12-18" BRS	41		4	25		41	70
Physocarpus capitatus	Pacific Ninebark	15'	18"-36" BRS	6'		2	7		0	9
Ribes sanguineum	Red-flowering currant	6'	18"-36" BRS	6'			11		41	52
Rosa nutkana var. nutkana	Nootka rose	8'	18"-36" BRS	4'		9	25		41	75
Rubus parviflorus	Thimbleberry	6'	18"-36" BRS	41		2	25		28	55
Rubus spectabilis	Salmonberry	8'	36"+ BRS	41		9	8		28	17
Salix hookeriana	Dune willow	10'	4' Live Stakes	41	17			36		53
Salix lucida ssp. lasiandra	Pacific willow	25'	4' Live Stakes	4'	22			36		58
Salix scouleriana	Scouler willow	25'	4' Live Stakes	4'	17			36		53
Salix sitchensis	Sitka willow	25'	4' Live Stakes	4'				36		36
Symphoricarpus albus	Snowberry	4'	36"+ BRS	4'					28	28
	·									766

SEED MIXTURE EC (EROSION CONTROL) 0.04 ACRES								
LATIN NAME	COMMON NAME	MATURE HEIGHT	PERCENT SPECIES COMPOSITION	PLS POUNDS PER ACRE				
Achillea millefolium	Yarrow	24"	0.05	0.04				
Bromus carinatus	California brome	24"	0.15	6.34				
Deschampsia caespitosa	Tufted hairgrass	24"	0.3	0.51				
Elymus glaucus	Blue wildrye	12"	0.35	11.91				
Lupinus rivularis	Riverbank lupine	12"	0.05	7.50				
Triticum aestivum	Regreen	24"	0.1	34.86				

PLANTING ZONE AREAS (SQUARE FEET							
	NC	RB2	RB3	WS3	UB2	Г	
	(NARROW	(RIPARIAN	(RIPARIAN	(WETLAN	(UPLAND		
	CHANNEL)	BUFFER)	BUFFER)	D SHRUB)	BUFFER)		
TOTAL AREA	862	1243	2715	6599	5110		
ESTIMATE OF EXISTING NATIVE VEGETATION TO PRESERVE	86	622	407	3300	1278		
PLANTING AREA (WEED CONTROL AND BARE GROUND)	776	622	2308	3300	3833		

PLANTING NOTES

- 1. SEEDING SHALL BE APPLIED PER SECTION 8.02(3)B. SEEDS SHALL HAVE GOOD SOIL CONTACT.
- 2. SEEDING SHALL OCCUR BETWEEN SEPTEMBER 15TH AND OCTOBER 31ST PRIOR TO INSTALLATION OF PLANT MATERIAL.
- 3. PLANT MATERIAL SHALL BE INSTALLED BETWEEN OCTOBER AND MARCH ACCORDING TO SECTION 9-14.2.
- 4. DUE TO FLOODPLAIN INUNDATION, NO MULCH SHALL BE PLACED BELOW THE ORDINARY HIGH WATER (OHW) LINE (MARKED IN FIELD. ARBORIST WOOD CHIP MULCH SHALL ONLY BE PLACED ABOVE THE OHW LINE.
- 5. INVASIVE SPECIES WITHIN THE PLANTING AREAS SHALL BE REMOVED AND TREATED PER CITY CODE PRIOR TO PLANTING. HIMALAYAN BLACKBERRY (RUBUS ARMENIACUS), JAPANESE KNOTWEED (POLYGONUM CUSPIDATUM), ENGLISH IVY (HEDERA HELIX) AND REED CANARYGRASS (PHALARIS ARUNDINACEA) AREA THE PRIMARY INVASIVE WEED SPECIES PRESENT ON SITE.
- 6. EXISTING TREES SHALL BE PROTECTED DURING CONSTRUCTION. AN APPROVED TREE PROTECTION PLAN SHOULD BE ESTABLISHED PRIOR TO THE START OF THE PROJECT.
- SQUARE FOOTAGE CONSIDERS EXISTING CANOPY COVER OF NATIVE TREE AND SHRUB SPECIES. SQUARE FOOTAGE ON PLANT SCHEDULE REFLECTS THE ESTIMATION OF PLANTING AREA AFTER INVASIVE SPECIES REMOVAL, NOT THE SQUARE FOOTAGE OF THE ENTIRE AREA.
- ** ROCKY MOUNTAIN GLOW MAPLE IS NOT INCLUDED IN ANY ZONES, AS IT IS THE PROPOSED STREET TREE ALONG 25TH AVENUE.





17500 Midvale Ave. N Shoreline, WA 98133 (206) 801-2700


NE 195TH STREET BALLINGER CREEK 60% REVIEW SUBMITTAL CULVERT REPLACEMENT PLANT SCHEDULE



12/30/2019 8:26 PM - PLOT DATE

Call before you dig





PROJECT LAYOUT - STRUCTURES

GENERAL NOTES

- ALL MATERIAL AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE WASHINGTON STATE DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR ROAD, BRIDGE AND MUNICIPAL CONSTRUCTION - DATED 2020, AND AMENDMENT EXCEPT AS NOTED BELOW.
- THIS STRUCTURE HAS BEEN DESIGNED IN ACCORDANCE WITH THE REQUIREMENTS OF THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, 8TH EDITION, UNLESS NOTED OTHERWISE.
- UNLESS OTHERWISE SHOWN ON THE PLAN, THE CONCRETE COVER MEASURED FROM THE FACE OF THE CONCRETE TO THE FACE OF ANY REINFORCING STEEL SHALL BE 2".
- ALL DIMENSIONS ARE HORIZONTAL AND VERTICAL UNLESS OTHERWISE SHOWN.
- EXISTING GROUND LINE IS APPROXIMATE AND SHALL BE VERIFIED BY THE CONTRACTOR IN THE FIELD.
- EXISTING STRUCTURES ARE SHOWN ON THE PLANS WITH APPROXIMATE LOCATIONS AND DIMENSIONS BASED ON THE AVAILABLE AS-BUILT INFORMATION. THOSE SHALL BE VERIFIED BY THE CONTRACTOR IN THE FIELD. ANY DISCREPANCIES LEADING TO SPATIAL CONFLICTS WITH NEW STRUCTURES SHALL BE REPORTED TO THE ENGINEER FOR REVIEW AND RESOLUTION.
- THE DESIGN IS BASED ON GEOTECHNICAL MEMORANDUM TITLED: DRAFT PRELIMINARY GEOTECHNICAL ENGINEERING REPORT 25TH AVENUE NE FLOOD REDUCTION, FILE NO. ______, DATED SEPTEMBER 6TH, 2 , DATED SEPTEMBER 6TH, 2016 AND OTHER CORRISPONDANCES WITH THE PROJECT GEOTECHNICAL ENGINEER, TERRACON CONSULTANTS, INC.
- CONTRACTOR SHALL COORDINATE BOX CULVERT WIDTHS WITH TOTAL WIDTH REQUIRED FOR EACH PHASE OF ELEMENT (OPEN CULVERT, WALL, CULVERTS, ETC.) CONSTRUCTION.

TEMPORARY LAGGING

SAWN LUMBER SHALL CONFORM TO THE REQUIREMENTS OF THE WEST COAST LUMBER INSPECTION BUREAU (WCLIB), SECTION 123-b. LUMBER SHALL BE UNTREATED AND CONFORM TO THE SPECIES AND GRADE NOTED

GRADE

SOLDIER PILE WALL LAGGING DOUGLAS FIR-LARCH NO. 2 OR BETTER

SIZE CLASS:

BEAMS AND STRINGERS

BENDING DESIGN VALUE:

Fb = 900 PSI

4x PER GEOTECHNICAL MEMORANDUM EXCEPT AS NOTED OTHERWISE. THICKNESS:

- THE CONTRACTOR SHALL EXCAVATE THE WALL FACE AND INSTALL THE LAGGING IN SUCH A MANNER AS TO MAINTAIN A SAFE WORK PLACE AND AVOID EXCESSIVE SLOUGHING AND OVERBREAK. AS A MINIMUM, PRIOR TO PLACING THE SUBSEQUENT SET OF TIMBER LAGGING, THE CONTRACTOR SHALL NOT EXCAVATE MORE THAN 3 FEET BELOW THE CURRENT DEPTH OF LAGGED WALL FACE
- LAGGING SHALL BE PLACED WITHIN 1 HOUR OF FACE EXCAVATION. OVER-EXCAVATED ZONES BEHIND LAGGING BOARDS SHALL BE BACKFILLED WITH FREE-DRAINING MATERIAL.
- TEMPORARY PRECAST LAGGING (SEE WALLS W2 & W3) SHALL BE BASED ON PLANS & SPECIAL PROVISION 6.16.3(6)B.

STRUCTURAL CONCRETE

CONC CLASS	LOCATION	COMPRESSIVE STRENGTH AT 28 DAYS f'c [PSI]	MIN COMPRESSIVE STRENGTH AT RELEASE
-	PUMPABLE LEAN CONCRETE	-	-
4,000	PRECAST CONCRETE	4,000 PSI	**
4,000	ALL OTHER	4,000 PSI	2,500 PSI *

SEE STANDARD SPECIFICATIONS FOR MINIMUM CURING TIME BASED ON CONTRACTOR'S RELEASE & LIFTING DESIGN

REINFORCING STEEL


STEEL REINFORCEMENT SHALL CONFORM TO THE FOLLOWING STANDARDS AND SPECIFIED STRENGTH.

REINFORCEMENT	AASHTO STANDARD	GRADE
DEFORMED BARS	M31	60
PLAIN WIRE (WELDED)	M55	70
PRESTRESSED REINFORCEMENT	M203	270

STRUCTURAL STEEL

SECTION	STANDARD	GRADE	STRENGTH
ANGLES & PLATES	ASTM A36	36	Fy=36 KSI
PLATES WHERE INDICATED	ASTM A572	50	Fy=50 KSI
PIPES	ASTM A53	В	Fy=35 KSI
WIDE FLANGE	ASTM A992	50	Fy=50 KSI
ANCHOR RODS	ASTM F1554	36	Fy=36 KSI

LEGEND



12/31/19 12/31/19 12/31/19 DES CHK





City of Lake Forest Park 17425 Ballinger Way NE Lake Forest Park, WA 98155

(206) 368-5440

NE 195TH STREET BALLINGER CREEK CULVERT REPLACEMENT 60% REVIEW SUBMITTAL

STRUCTURAL SHEET LAYOUT GENERAL NOTES


- IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES.



vroject No. WA16.0261.00

Know what's below. Call before you dig.

23 Of



Know what's below. Call before you dig.

PRELIMINARY


12/5/2019 2:13 PM - PLOT DATE

S-2

60% REVIEW SUBMITTAL
STRUCTURAL LAYOUT
SHEET 1

1: IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORD

Sheet 24 Of 36



PRELIMINARY

Project No. WA16.0261.00 $\frac{80}{2}$

S-3

Know what's below.
Call before you dig.
Sheet 25 Of 36

Date 12/31/19 12/31/19 12/31/19

DRW DES CHK

WSP USA Inc. 33301 9th Avenue South Suite 300

City of Lake Forest Park

(206) 368-5440


NE 195TH STREET BALLINGER CREEK CULVERT REPLACEMENT


60% REVIEW SUBMITTAL
STRUCTURAL LAYOUT
SHEET 2

1". IF NOT ONE INCH ON THIS SHEET, SCALES ACCORDI

17425 Ballinger Way NE Lake Forest Park, WA 98155

Federal Way, WA 98003-2600 TEL: (206) 431-2300 FAX: (206) 431-2250





ELEVATION - WALL W1

Date 12/31/19 12/31/19 12/31/19 DRW DES CHK

WSP USA Inc. 33301 9th Avenue South Suite 300 Federal Way, WA 98003-2600 TEL: (206) 431-2300 FAX: (206) 431-2250




City of Lake Forest Park 17425 Ballinger Way NE Lake Forest Park, WA 98155 (206) 368-5440

NE 195TH STREET BALLINGER CREEK CULVERT REPLACEMENT

60% REVIEW SUBMITTAL
WALL ELEVATIONS
SHEET 2

1". IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORD

Project No. WA16.0261.00 $\frac{80}{2}$



Date 12/31/19 12/31/19 12/31/19 DRW DES CHK

WSP USA Inc. 33301 9th Avenue South Suite 300 Federal Way, WA 98003-2600 TEL: (206) 431-2300 FAX: (206) 431-2250




17425 Ballinger Way NE Lake Forest Park, WA 98155 (206) 368-5440

NE 195TH STREET BALLINGER CREEK CULVERT REPLACEMENT

60% REVIEW SUBMITTAL
WALL ELEVATIONS
SHEET 3

1: IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORD



Project No. WA16.0261.00

Know what's below. Call before you dig.

City of Lake Forest Park 17425 Ballinger Way NE Lake Forest Park, WA 98155 (206) 368-5440

Lake Forest Park, WA 98 (206) 368-5440

NE 195TH STREET BALLINGER CREEK CULVERT REPLACEMENT

60% REVIEW SUBMITTAL

WALL ELEVATIONS
SHEET 4

71. IF NOT ONE INCH ON THIS SHEET. ADJUST SCALES ACCORDING


C. BEIGHT


Project No. WA16.0261.00

Sheet S-7


S-729 Of 36

PRELIMINARY





SECTION - CULVERT C1 EXCAVATION




CULVERT C1 EXCAVATION DETAIL

NOTES TO DESIGNER:

- 1. NEED TO DETERMINE FENCE OR RAILING AT 195TH.
- 2. NEED TO SPECIFY SUPPORT OF 66" WATER LINE FROM WALLS CW-1A AND CW-1B.

PRELIMINARY





30 Of


Date 12/31/19 12/31/19 12/31/19 DRW DES CHK


WSP USA Inc. 33301 9th Avenue South Suite 300 Federal Way, WA 98003-2600 TEL: (206) 431-2300 FAX: (206) 431-2250




17425 Ballinger Way NE Lake Forest Park, WA 98155 (206) 368-5440

NE 195TH STREET BALLINGER CREEK CULVERT REPLACEMENT 60% REVIEW SUBMITTAL CULVERT C1
PLAN & ELEVATION
OT ONE INCH ON THIS SHEET, ADJUST SC.







SOLDIER PILE / EXISTING CULVERT INTERFERENCE DETAIL

PRELIMINARY

Project No. WA16.0261.00 Know what's below.
Call before you dig.
Sheet 32 Of 36

PRECAST WALL INSTALLATION DETAIL

NE 195TH STREET BALLINGER CREEK CULVERT REPLACEMENT


Date 12/31/19 12/31/19 12/31/19

DRW DES CHK

WSP USA Inc. 33301 9th Avenue South Suite 300 Federal Way, WA 98003-2600 TEL: (206) 431-2300 FAX: (206) 431-2250


City of Lake Forest Park 17425 Ballinger Way NE Lake Forest Park, WA 98155 (206) 368-5440


60% REVIEW SUBMITTAL



SHOWN FOR SOLDIER PILE WITH P.G.A. AND TIEBACK ANCHOR SIMILAR FOR SOLDIER PILE WITHOUT P.G.A.

P.G.A.= PERMANENT GROUND ANCHOR





Know what's below.

Call before you dig.



33 Of 36 12/5/2019 2:14 PM - PLOT DATE

vroject No. WA16.0261.00 €

S-11

WSP USA Inc. 33301 9th Avenue South Suite 300

Federal Way, WA 98003-2600

17425 Ballinger Way NE

(206) 368-5440

NE 195TH STREET BALLINGER CREEK CULVERT REPLACEMENT

60% REVIEW SUBMITTAL SOLDIER PILE DETAILS - SHEET 1 OF

Lake Forest Park, WA 98155

PRELIMINARY